




O. Napoly, CEA-Saclay, Irfu/SACM


- Introduction to the XFEL goals
- The electron linac
- Cryomodule production and performance
- Conclusions



## XFEL = X-ray Free Electron Laser

- 4<sup>th</sup> generation light source
- FEL in SASE mode
- Tunable wave-length > 0.5 Å
- 10-100 fs light pulse duration
- Spatial coherence
- Cost : ~1 G€










## Some specifications

- Photon energy  $0.25 \rightarrow 25$  keV
- Pulse duration  $\sim 10\text{--}100$  fs
- Pulse energy few mJ
- Superconducting linac 17.5 GeV
- 10 Hz (27 000 b/s)
- 5 beamlines / 10 instruments
  - Start version with 3 BLs and 6 instruments
- Several extensions possible:
  - Self-Seeding
  - More undulators
  - More instruments
  - ....
  - CW operation



**Self Amplification of Spontaneous Emission (SASE)  
Free Electron Lasers (FELs) for hard X-Rays (~0.5 - 60 Å)**




Basic Principle:

Self modulation of electron bunch density by own electro-magnetic field

⇒ micro-bunching

⇒ Electrons radiate in phase:  $P \sim N^2$




Need extremely good electron beam quality:

- Small emittance
- Small energy spread
- Large energy
- High particle densities

## SASE – Self-Amplified Spontaneous Emission

Kondratenko, Saldin (1979)

Bonifacio, Pellegrini, Narducci (1984)




Need extremely good electron beam quality:




- Small emittance
  - Small energy spread
  - Large energy
- $\gamma = 34 \times 10^3$  @ 17,5 GeV

**First principle: production of hard X-Rays**

- Electron bunch oscillation period in lab frame is  $\lambda_u/c$
- Electron bunch oscillation period in its rest frame is  $\lambda_u/\gamma c$ , due to Lorentz time dilatation
- Radiation at  $\gamma c/\lambda_u$  frequency in rest frame
- Photon radiation frequency in lab frame is  $\gamma^2 c/\lambda_u$  due to the relativistic Doppler effect.
- Wavelength  $\sim \lambda_u/\gamma^2$  in laboratory frame




**Second principle: ‘micro-bunching’**  
Radiation electric field has a small component parallel to electron velocity, which can accelerate or decelerate electrons



Third principle: coherent radiation (*T. Shintake*)

Micro bunches are coherent at the  $\lambda_x$  scale, they radiate as a 'macroscopic' charge




$$\lambda_r = \frac{\lambda_u(1+K^2)}{2\gamma^2} \rightarrow 1-9$$

$\lambda_r$  ↓  
 $1 \times 10^{-10} \text{ m}$

$40-68 \text{ mm}$


$$K = 0.094B_0[T]\lambda_u[\text{mm}]$$

European XFEL aims at 0.25 to 25 keV





**Hard X-rays****SPB/SFX: Single Particles, Clusters, and Biomolecules****Serial fs Crystallography**


- Structure determination of single particles: atomic clusters, bio-molecules, virus particles, cells.

**MID : Materials Imaging & Dynamics**


- Structure determination of nano-devices and dynamics at the nanoscale.

**FXE : Femtosecond X-ray Experiments**

- Time-resolved investigations of the dynamics of solids, liquids, gases

**HED : High Energy Density Matter**


- Investigation of matter under extreme conditions using hard X-ray FEL radiation, e.g. probing dense plasmas

**SQS: Small Quantum Systems**

Investigation of atoms, ions, molecules and clusters in intense fields and non-linear phenomena

**SCS: Soft x-ray Coherent Scattering/Spectroscopy**

Electronic and real structure, dynamics of nano-systems and of non-reproducible biological objects










Courtesy M. Altarelli

## Applied to larger and larger complex molecules:

**Lysozyme**

(Enzyme from poultry)

**X-rays****Crystal****Detector****Determination of the atomic structure of the molecule!**

Courtesy M. Altarelli


In spite of its extraordinary success, synchrotron bio-crystallography meets some limitations:

Need for crystals > (10-100 µm)<sup>3</sup>

Radiation damage limits resolution... freezing a partial remedy


Crystal of Bovine Enterovirus 2 (BEV 2), 0.5 s, 10<sup>8</sup> ph/µm<sup>2</sup>

D. Axford et al., Acta Cryst D68, 592 (2012)




Courtesy M. Altarelli

Speed may be the answer!  
“Diffraction before destruction”



R. Neutze, R. Wouts, D. van der Spoel, E. Weckert, J. Hajdu, Nature **406** (2000)

101 cryomodules




808 cavités  
1.3 GHz / 23,6 MV/m




808 coupleurs RF  
120 kW @ 5 mA




26 stations RF (10 MW)  
opérant à 5,2 MW



1 secteur cryogénique (12 modules) : 120 W @2K, 204 W @5-8K, 1,4 kW @40-80K




# Installation Status Linac Tunnel



- **Accélérateur linéaire supraconducteur à électrons**
- Haute énergie : 17,5 GeV
- Taux de répétition : 10 Hz
- Impulsion : 650 µs de faisceau, 1,4 ms de RF
- Intensité moyenne : 0,25-5 mA (0,02 - 1 nC / 200 ns)
- Intensité crête : 5 kA (un paquet)
- Emittance normalisée : 1,4 Pi mm.mrad


Quantity	Value
electron energy	8/12.5/14/17.5 GeV
macro pulse repetition rate	10 Hz
RF pulse length (flat top)	600 $\mu$ s
bunch repetition frequency within pulse	4.5 MHz
bunch charge	0.02 – 1 nC
electron bunch length after compression (FWHM)	2 – 180 fs 90 fs
Slice emittance <b>(relates to gun RF power)</b>	0.4 - 1.0 mm mrad
beam power	500 kW

## Electron bunch trains (with up to 2700 bunches, 0.1–1 nC)



## Dedicate & distribute electron bunches to instruments

- Operate accelerator as continuous as possible  
→ stability / performance
- Distribute electron bunch train on two lines  
→ 10 Hz switch (few  $\mu$ s duration)
- Switch on/off lasing for SASE 1/ SASE 3 line (optional)  
→ 4.5 MHz switches
- Determine exact bunch pattern  
→ 4.5 MHz switch



Electron bunch distribution : 27.000 bunches/sec to 3 (5) beamlines; in average 10-20 Hz and ~800 (500) pulses/train;  
using kicking methods to make bunches lase only in dedicated undulator


## Champ accélérateur ('gradient') G maximal vs. G utile


- Minimum of the following gradient values:
  - MAX (i.e. quench)
  - $Q_0 = 10^{10}$
  - X-ray 1 (top) threshold
  - X-ray 2 (bottom) threshold

$$Q_0 = \omega_{RF} W / P_{\text{diss}}$$

In this example, usable gradient is limited by FE (X-ray<sub>1</sub>) to ~27 MV/m

Courtesy M. Wiencek, N. Walker





## E-XFEL Module Assembly ‘Phase Diagram’

RF Test and Linac operation limited to 31 MV/m to protect the RF distribution system

Courtesy N. Walker

	N <sub>cavs</sub>	Average	RMS	min	max
VT	615.	30.2	4.6	11.2	43.7
CM	615.	27.6	4.6	10.5	31.






Courtesy D. Reschke

**La contribution du CEA à European-XFEL:**  
**assemblage de 103 cryomodules**  
**sur le site de Saclay et l'infrastructure du CEA**




**opéré par un contractant industriel Alsyom:**

- **Objectif de production : 1 module / semaine**
- **Objectif de performance :  $E_{acc} > 23,6 \text{ MV/m}$**
- ⇒ **Objectif global:  $V_{acc} > 196 \text{ MV par semaine}$**


**Cryo-systems****Vacuum vessels****Magnetic Shields / CEA**

**Couplers / IN2P3  
670 Thales-RI  
150 CPI**

**Quadrupole-BPM / DESY  
103 Magnets / Ciemat  
BPM / 72 DESY – 31 CEA  
206 Gate Valves / DESY**



**Helium tanks / DESY  
600 Zanon / 200 CNC / DESY**


**Tuners / DESY****Current leads / DESY**

## Cryo-systems



Vacuum vessels

## Warm ceramic



## Couplers / IN2P3

650 Thales-RI


150 CPI

Quadrupole-BPM / DESY  
103 Magnets / Ciemat  
BPM / 72 DESY – 31 CEA  
206 Gate Valves / DESY

9 422 components integrated

and more than 12 400 individual parts manipulated  
per cryomodule.

45 from Zanon, 58 from IHEP/DESY




Magnetic Shields / CEA


800 Cavities / DESY  
400 Zanon / 400 RI




Current leads / DESY









# Halls d'Assemblage: Stations de Travail








Assemblage de la masse froide (RO-WS)




**Stations Masse froide (RO-WS) et Alignement des cavités (AL-WS)**



XM1 (enfourneur) le 14/02/2014




Assemblage des coupleurs  
chauds (CO-WS)



XM1 (Enfourneur) and XM-1 (Coupleurs chauds) le 14/02/2014



Expédition (SH-WS)



Chargement (SH-WS)






Figure: expédition des cryomodules de série, de XM1 à XM100

- **93 cryomodules livrés à DESY à ce jour (XM-3, XM-2, XM-1 inclus).**
- Depuis Janvier 2015, la cadence d'expédition est de **4 jours**.
- Le linac inclut les modules de pré-séries XM-2 et XM-1, mais pas XM-3
- L'expédition de XM100 est prévue le **5 juillet 2016**


Average operating gradient per cryomodule, clipping the VT results to 31 MV/m



- All but 5 of 85 tested modules are on XFEL specs (23.6 MV/m), 6 modules need(ed) repair.
- Average gradient is 17% above specs :  $\langle E_{acc} \rangle = 27.7 \text{ MV/m}$ .
- Significant gradient degradation from XM6 to XM23, while CEA and Alsyom put all their effort in achieving production goal of 1 CM/week: **an audit of string and module assembly was conducted by CEA on XM26**
- A simplification of the clean room procedures was introduced at XM54: **no degradation after**



XM4 cavities:



## XM4 cavities: sp test at CMTB (Denis Kostin)

Gradients	Cavity	Max Eacc [MV/m]	Max oper. Eacc [MV/m]	Operation Limit
	C1_0626	33.5	31.0	PWR
	C2_0607	34.8	31.0	PWR
	C3_0556	31.1	30.6	Quench
	C4_0597	34.5	29.9	X-ray > $10^{-2}$ mGy/min
	C5_0606	<b>39.0</b>	31.0	PWR
	C6_0621	24.4	23.9	Quench
	C7_0592	<b>22.0</b>	21.5	Quench
	C8_0594	35.1	31.0	PWR


Qo(2K)

Eacc [MV/m]	15	20.5
$\langle Qo \rangle [10^{10}]$	2.4	2.3 (?)

## cw tests at 2K, FCD &amp; SCD

1,E+11

Qo



In most of runs 3 methods (3M) were used to determine  $E_{acc}$  (to minimize an error): Read out of pickups (calibrated the sp mode),  $\{P_{in}, Q_{load}\}$  for each cavity, and IOT ( $P_{IOT} * 0.95 / 8$ ).

- E-XFEL Cryomodule Assembly at Saclay went through 4 main phases:
  1. Mastering the process [ T1/2008 – T1/2013 ]
  2. Mastering the infrastructure and tooling [ T3/2010 – T1/2013 ]
  3. Mastering the handling of non-conformities, both *imported*-PRODUCT and PROCESS-generated non-conformities [ T3/2012 – T3/2014 ]
  4. ‘Mastering’ the industrial operator
    - Productivity [ T1/2014 – T4/2014 ]
    - Quality Assurance [ T4/2014 – ongoing ]

This process depends inevitably on the early availability of the cryomodule components: ‘*Practice makes perfect*’

- The difficulties of coupler assembly had been under-estimated by CEA
  1. e.g. cavity vs. coupler assembly includes 1 vs. 12 individual parts,  
~100 vs. ~1000 fastening hardware.
  2. about 8 couplers (both cold part and warm part) have been destroyed  
due to bad manipulation and/or bad assembly.
- Better module RF performance correlated to Clean Room practice and procedures.

---

# Thank you for your attention